KOLAR DIVISION.

Dated 22nd February 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 16th March 1931, for restoring Asali Attikunte Kannappanakere, R. No. 164 of Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar in Drawing Branch, between the hours of 11 A.M. to 5 P.M., office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in form given below, showing the rates at which the different items specified will be executed.

4. Each tender should be accompanied by a deposit of Rupees one hundred and forty in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Asali Attikunte Kannappanakere, R. No. 164 of Mulbagal Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of the work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate of quantities for restoring Asali Attikunte Kannappanakere, Registered No. 164 of Mulbagal Taluk.

No.	Items of work	Per	Quantity
	Bund R. L. 57·00—		
1	Earthwork to bund with watering and consolidating including lead and lift.	C.yd.	3,765
2	New stone work	,,	209
2a	Removing and resetting old stone with jelly	,,	23
3	Turfing the bund	S.yd.	2,934
4	Jungle clearing and removing trees with roots and prickly pears.	Grade	3
5	Removing top tail and ant hills and cutting grips ...	,,	11
6	Removing and refixing old grade stones with necessary painting, etc., complete.	Each	12
7	Removing and refixing Index stones with necessary painting, etc., complete.	,,	12
8	Providing new Registered No. stone with painting, etc., complete.	,,	1
9	Painting B. M. stones do do ...	,,	2
10	Providing new gauge stone with painting, etc., complete...	,,	1
	Sluice—		
1	Providing new plug with iron rod and locking arrangements and sundry repairs to masonry.	L. S.	Rs.
	Weir—		
1	Dismantling the brick masonry	C.ft.	23
2	Burnt brick in surki mortar	,,	264
3	Concrete in surki mortar	,,	20
4	Removing and relaying available burnt stone slabs with Joggles joints, etc., complete.	S.ft.	88
5	New burnt stone slabs 6" thick dressed	,,	157
6	Plastering with surki mortar	Sqr.	3·13
7	New stone work	C.yd.	143
8	Removing and resetting old stone work with jelly ...	,,	57
9	Filling jelly for the old apron portion to ensure proper	,,	107

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 16th March 1931, for restoring Marapanhalli Hosakere R. No. 303, Serial No. 142 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees..... in Cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Restoring Marapanhalli Hosakere R. No. 303 Serial No. 142 of Malur Taluk, Kolar District in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond . in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderers must quote specific rates for each item of the work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate of quantities for Restoring Marapanhalli Hosakere Registered No. 303 Serial No. 142 of Malur Taluk.

Sl. No.	Items of work	Per	Quantity
	Bund.		
1	Earthwork to bund watering and tamping including lead and lift, complete.	C.yd.	2,348
2	Turfing to bund	Syd.	2,513
3	Removing and resetting old stone with new jelly ...	C.yd.	531
4	New stone work to required level with jelly	,,	402
5	Providing and fixing new grade stones and painting, etc. ...	Each	11
6	Index stones do do ...	,,	11
7	Bench mark stones	,,	2
8	Registered No. stones	,,	1
9	Gauge stone	...	1
	Sluice.		
1	Earthwork excavation for sluice	C.yd.	57
2	Refilling the same with watering and tamping	,,	46
3	Surki concrete for foundation	C.ft.	334
4	Burnt brick in surki mortar	,,	188
5	Burnt stone slabs 4" to 6" thick	S.ft.	305
6	Plastering with surki mortar	Sqr.	3·43
7	Providing wooden plug and rod and locking arrangement ...	No.	1
8	Cutting holes in orifice and cill slabs	Each	3
	Waste weir.		
1	Earthwork excavation for body wall and return ..	C.yd.	44
2	Surki concrete for foundation	C.ft.	167
3	Burnt brick in surki mortar	,,	268
4	Burnt stone slabs 4" to 6" thick	S.ft.	245
5	Plastering with surki mortar	Sqr.	2·80
6	New stone for apron	C.yd.	28